



Bauaufsichtlich anerkannte Stelle
für Prüfung, Überwachung und
Zertifizierung
Zulassung neuer Baustoffe, Bauteile
und Bauarten
Forschung, Entwicklung,
Demonstration und Beratung auf
den Gebieten der Bauphysik

Institutsleitung
Univ.-Prof. Dr. Gerd Hauser
Univ.-Prof. Dr. Klaus Sedlbauer

Test report P-BA 288/2007e

Determination of the Acoustic Performance of a Wastewater Installation System in the Laboratory

Client: NUEVA TERRAIN S. L.
Paduleta, 2
01015 VITORIA
SPAIN

Test specimen: Wastewater installation system consisting of "TERRAIN SDP STANDARD PVC, 110x3.2" plastic pipes (manufacturer: NUEVA TERRAIN S. L.) mounted with pipe clamps "sound proof support bracket" (manufacturer: REHAU).

Contents: Table 1: Summary of test results
Figures 1 to 3: Detailed results
Figure 4: Installation plan
Annex A: Measurement set-up, noise excitation, acoustic parameters
Annex F: Evaluation of measurements
Annex P: Description of test facility

The tests were performed in a laboratory accredited by the German Accreditation System for Testing (DAP, file no. PL-3743.26) according to standard EN ISO/IEC 17025.

Any publication of this document in part is subject to written permission by the Fraunhofer Institute of Building Physics (IBP).

Stuttgart, December 19, 2007

Responsible Test Engineer: Head of Laboratory:


Dipl.-Ing.(FH) J. Mohr


Dr. rer. nat. L. Weber

Determination of the installation sound level L_{in} in the laboratory

P-BA 288/2007e

Table 1

- Client:** NUEVA TERRAIN S. L., Paduleta, 2, 01015 VITORIA, SPAIN
- Test specimen:** Wastewater installation system (test specimen S 9961-01) consisting of "TERRAIN SDP STANDARD PVC, 110x3.2" plastic pipes and fittings (manufacturer: NUEVA TERRAIN S. L.) mounted with pipe clamps "sound proof support bracket" (manufacturer: REHAU).
- Test set-up:**
- The pipe system was mounted according to Figure 4 (see also Annex A).
 - The system consisted of wastewater pipes (nominal size OD 110), three inlet tees (45°), two 45°-basement bends and a horizontal drain section. The inlet tees in the basement and in the ground floor were closed by lids supplied by the manufacturer. The pipe system was mounted by a technical firm.
 - Pipe system "TERRAIN SDP STANDARD PVC, 110x3.2": size OD 110, one-layer pipe with attached sleeve, material: PVC, wall thickness 3.2 mm, weight 1.64 kg/m, density 1.45 g/cm³. One-layer fittings "TERRAIN SDP STANDARD PVC, 110x3.2", size OD 110, material: PVC, wall thickness 3.2 mm, density 1.45 g/cm³. Connection of the pipes by plug-on socket connection. (Values are manufacturer's information.)
 - Pipe clamps "sound proof support bracket" consisting of supporting and fixing clips and loose clips, all with rubber inlay. The pipe clamps were fixed to the installation wall with dowels and thread rods.
- Test facility:** Installation test facility P12, mass per unit area of the installation wall: 220 kg/m², installation rooms: sub-basement (KG), basement (UG) front, ground floor (EG) front and top floor (DG), measuring rooms: UG front, UG rear (details in Annex P and EN 14366: 2005-02)
- Test method:** The measurements were performed following German standard DIN 52 219: 1993-07 and EN 14366; noise excitation by permanent water flow with 0.5 l/s, 1.0 l/s, 2.0 l/s and 4.0 l/s (details in Annexes A and F).

Results:

Waste water system " TERRAIN SDP STANDARD PVC, 110x3.2" with pipe clamps "sound proof support bracket"					
	Flow rate [l/s]	0,5	1,0	2,0	4,0
Installation sound level L_{in} [dB(A)] measured in the basement test-room UG front		44	49	51	54
Installation sound level L_{in} [dB(A)] measured in the basement test-room UG rear		4	8	13	18
Airborne sound pressure level $L_{a,A}$ [dB(A)] ¹⁾		44	49	51	54
Structure-borne sound characteristic level $L_{sc,A}$ [dB(A)] ¹⁾		1	5	10	14

¹⁾ Evaluation according to EN 14366.

- Date of tests:** November 5, 2007
- Comments:** - The requirements of DIN 4109 only apply for the installation sound level L_{in} measured in the test room UG rear.



The tests were performed in a laboratory accredited by the German Accreditation System for Testing (DAP, file no. PL-3743.26) according to standard EN ISO/IEC 17025.
 Stuttgart, December 19, 2007
 Head of Laboratory: 